FAZA 1

Izvedba športnega poda , kot npr.: BOEN BOFLEX



CONNEXPROCESS



UNLOADED

The parquet rests on each alternate Evazote strip.

LIGHTLY LOADED



The parquet rests on each alternate Evazote strip.

NORMAL LOAD

Whether all or alternate Evazote strips are under restrain is dependant on the type of sport.

HEAVY LOADS



The way in which the Evazote is constructed means that it can never be compressed more than 50%. The floor can withstand several tons of pressure without any damage being done.

OPOMBA: Zahtevana ravnost končnega tlaka brušenega betona (TK 01) je definirana s standardom za ravnost tal DIN 18202 - tabela 3
po grupi 4.

Flatness Specification: DIN 18202 – Table 3

Table 3: Flatness tolerances

Column	1	2	3	4	5	6
Group	Applicable to	Position deviations (limit values), in mm, for distances between measuring points, in m, up to				
		0.1	1 *	4 *	10 *	15 * †
1	unfinished upper surfaces of floors, subfloors and concrete bases	10	15	20	26	30
2	unfinished upper surfaces of floors, subfloors and concrete bases subject to more stringent requirements (e.g. to receive bonded screed, industrial floors, tile flooring and bonded screed), and finished surfaces for minor purposes (e.g. in storerooms or basements)	5	8	12	16	20
3	finished floors (e.g. screed as wearing courses or screed to receive a flooring, trowelled or bonded floorings)	2	4	10	12	15
4	As group 3, but subject to more stringent requirements	1	3	9	12	15
5	unfinished walls and unfinished ceilings	5	10	15	25	30
6	finished walls and ceilings (e.g. plastered walls, wall claddings and linings, suspended ceilings)	3	5	10	20	25
7	As group 6, but subject to more stringent requirements	2	3	8	15	20

Intermediate values shall be taken from figures 1 and 2, and shall be given to the nearest millimetre.

† The flatness tolerances in column 6 also apply to distances between measuring points of over 15m.

Schluter Systems

Schluter®-DILEX-EHK

Schluter®-DILEX-EHK A

Schluter®-JOLLY

kuffner G60-8

Legenda tlakov:

TK 01	Brušen beton
TK 02	Dekorativni epoksi
TK 03	Športni parket
TK 04	Epoksi
TK 05	Brušen beton
TK 06	Parket
TK 07	Zunanji leseni pod

Legenda tlakov:

TZ 01	Kuffner
TZ 02	Leseni profil
TZ03	Schluter dilex AHKA
TZ 04	Zaokrožnica epoksi premaz

TK 01 TLAK KLET - BRUŠEN BETON

tlačna betonska plošča	8,0 cm
PE folija	
cementna estrihna zaključna plošča	7,0 cm
skupna debelina AKTA	**15,0 cm**

TK 02 TLAK KLET - KERAMIKA

tlačna betonska plošča	8,0 cm
kvarčni sloj, keramična ploščica	1,0 cm
cementna malta	3,5 cm
izravnalna masa	0,5 cm
mikrocementni cementni estrih	7,0 cm
PE folija	
toplotna izolacija - polivinilni pvc	10,0 cm
toplotna izolacija XPS	**30,0 cm**

TK 03 TLAK TELOVADNICA - ŠPORTNI POD

Športni parket	3,0 cm
mikrocementni cementni estrih	6,0 cm
protiudarna folija	
toplotna izolacija - EPS 150 ostenevska plošča, kot npr.	
PE folija	6,0 cm
toplotna izolacija XPS	10,0 cm
hidroizolacija- bitumenski trakovi	**25,0 cm**

TK 04 TLAK TEHNIČNEGA PROSTORA - EPOKSI

tlačna betonska plošča	8,0 cm
mikrocementni cementni estrih	8,0 cm
PE folija	
toplotna izolacija - polivinilni pvc	10,0 cm
toplotna izolacija XPS	**30,0 cm**

TK 05 TLAK PROTILČJA/NAGIB STROPA - BRUŠEN BETON

tlačna beton	8,0 cm
PE folija	
toplotna izolacija - polivinilni pvc	**10,0 cm**
toplotna izolacija XPS	

TK 06 TLAK PROTILČJA/NAGIB STROPA - PARKET

tlačna plošča	8,0 cm
mikrocementni cementni estrih	7,0 cm
PE folija	
toplotna izolacija - polivinilni pvc	10,0 cm
toplotna izolacija XPS	**25,0 cm**

TK 07 TLAK PROTILČJA nad talno ploščo - PARKET

tlačna betonska plošča	8,0 cm
mikrocementni cementni estrih	7,0 cm
PE folija	
toplotna izolacija - polivinilni pvc	6,0 cm
toplotna izolacija XPS	**10,0 cm**

TR8 TLAK TERASE

terazzo dročka - sibirski macesen	3,0 cm
mikrocementni cementni estrih	6,0 cm
PE folija	
toplotna izolacija XPS	6,0 cm
hidroizolacija - bitumenski trakovi	**25,0 cm**

TR9 TLAK TERASE

terazzo dročka - sibirski macesen	3,0 cm
cementni estrih	6,0 cm
podlaga beton 25 - 30 cmm	19,0 cm
lastniški naklon	
	28,0 cm

TH8 LAMELNI STRAC

tlačna betonska plošča	8,0 cm
toplotna izol. sajstra	9,5 cm
izravnalna masa	5,0 cm
mikrocementni cementni estrih	7,0 cm
PE folija	
toplotna izolacija XPS	3,0 cm
zidovska hidroizolacijska premaz	**2,5 cm**
	10,0 cm

PN - klet - tlaki

faze izgradnje	tlak	št. pr.	ime	površina
2. FAZA	ŠPORTNI PARKET	K 09	TELOVADNICA	1.377,25
3. FAZA	BRUŠEN BETON	K 25	OSTALA	3,79
3. FAZA	BRUŠEN BETON	K 23	POŽ. STOPNIŠČE	12,97
3. FAZA	BRUŠEN BETON	K 22	HODNIK TELOVADNICA	13,99
3. FAZA	BRUŠEN BETON	K 21	HODNIK	87,58
3. FAZA	BRUŠEN BETON	K 20	HODNIK OSTO	39,70
3. FAZA	BRUŠEN BETON	K 19	HODNIK NEČISTO	27,64
3. FAZA	BRUŠEN BETON	K 17	ORODJARNA	43,74
3. FAZA	DEKORATIVNI EPOKSI	K 16	SANITARIJE INVALIDI	8,46
3. FAZA	DEKORATIVNI EPOKSI	K 15	SANITARIJE MEŠANO	11,21
3. FAZA	DEKORATIVNI EPOKSI	K 15	M.SANITARIJE	13,15
3. FAZA	DEKORATIVNI EPOKSI	K 14	Ž.SANITARIJE	11,07
3. FAZA	DEKORATIVNI EPOKSI	K 13	GARDEROBE MEŠANO	8,23
3. FAZA	DEKORATIVNI EPOKSI	K 12	GARDEROBE MEŠANO	17,80
3. FAZA	DEKORATIVNI EPOKSI	K 11	GARDEROBE Ž.	16,78
3. FAZA	DEKORATIVNI EPOKSI	K 10	GARDEROBE M.	18,79
3. FAZA	DEKORATIVNI EPOKSI	K 10	GARDEROBE M.	8,22
3. FAZA	DEKORATIVNI EPOKSI	K 10	GARDEROBE M.	8,79
3. FAZA	PARKET	K 25	KABINET - UČITELJ TELOVADBE	7,39
3. FAZA	PARKET	K 24	KABINET - UČITELJ TELOVADBE	7,39

klet - tlaki KVADRATURE PO FAZAH

faze izgradnje	tlak	površina
2. FAZA	ŠPORTNI PARKET	1.377,25
3. FAZA	BRUŠEN BETON	219,07
3. FAZA	DEKORATIVNI EPOKSI	119,95
3. FAZA	PARKET	14,78

IES-01 PN - profili keramika

faze gradnje	oznaka	dolžina	količina
3. FAZA	Schluter-DILEX-EHK	1,64	1
3. FAZA	Schluter-DILEX-EHK	1,54	2
3. FAZA	Schluter-DILEX-EHK	2,50	18
3. FAZA	Schluter-JOLLY	1,64	1
3. FAZA	Schluter-JOLLY	1,54	2
3. FAZA	Schluter-JOLLY	2,50	3

klet - nizkotenski profili

faze gradnje	oznaka	dolžina
3. FAZA	TZ 01	187,34 m
3. FAZA	TZ 03	52,38 m
3. FAZA	TZ 04	33,44 m

SPECIMENS

STRNŠA ARHITEKTURA

STRNŠA ARHITEKTURA D.O.O.
T: +386 (0) 2 233 73 80 Ulica Vita Kraigherja 4a, SI-2104 Hoče-Slivnica
E: info@strnsa.si www.strnsa.si

Občina Miren-Kostanjevica

±0.00 = +47.98

objekt: **OŠ Miren in postavitev nove telovadnice**
PARCELNA ŠTEVILKA: Miren-Kostanjevica
k.o. 2201, parcele: parc. št. 4201/1 4201/2 4201/3 4201/4 4201/5 4201/6 4202 4203 4204 4205 4207, 4207/2, 4208, 4209, 4207, 4209, 4210, 4211 in del parc. št. 4206/1 in 4206/2

naročnik: **Občina Miren-Kostanjevica**
Mirje 137, Miren - Slovenija

vrsta načrta: **TLAKI**

projekt: **PZI - Projekt za izvedbo - 2+ FAZA**

faza: **Tloris tlakov - klet 2. F ZAČASNO**

datum: JANUAR 2021

št. projekta: **01/18**

odgovorni vodja projekta: David MIŠIČ, Mag. Arch. **ZAPS 1211**

odgovorni projektant: David MIŠIČ, Mag. Arch. **ZAPS 1211**

projektant: Jernej METEŽ, BA Ark. grad.
Urbanistika, Mirje 37, Ljubljana - Moste, tel.: 01 568 39 33

merilo: 1:50, 1:1 | št.dr. **3.1.1**